# Results from the LOFAR2.0 Dwingeloo Test Station



Boudewijn Hut and team

hut@astron.nl


Systems Engineer for the LOFAR Instrument Development Program



RON This publication is part of the project DUPLLO (with project number 175.2017.012 of the research programme "Investeringen NWO-groot" which is (partly) financed by the Dutch Research Council (NWO)









# The LOFAR Telescope in numbers

- 52 Stations
  - 4.992 Low Band Antennas
  - 50.688 High Band Antennas
    - 3.168 HBA Tiles
- Input data rate
  - LOFAR1: 14 Tbps
  - LOFAR2: 45 Tbps
- Central Processor
  - Correlator, beamformer, ..
  - Datawriter
- Long Term Archive





#### The LOFAR2.0 upgrade, the challenge



#### LOFAR2.0 Station Upgrade

• Limitation: One out of three antennas active

CORE STATION

- LOFAR2.0 will improve this
  - simultaneous Low + High Band observing
  - increased Low Band sensitivity
  - Improve linearity
- Challenge:
  - More power consumption
  - Keep station available on hot days

Central Processor

Station Cabine

REMOTE STATION

#### LOFAR2.0 Station Upgrade

• Limitation: One out of three antennas active


CORE STATION

- LOFAR2.0 will improve this
  - simultaneous Low + High Band observing
  - increased Low Band sensitivity
  - Improve linearity
- Challenge:
  - More power consumption
  - Keep station available on hot days

Central Processor


Station Cabine

REMOTE STATION



# LOFAR2.0 Verification and Validation

<ul> <li>Test phase</li> </ul>	S				
	Lab Test Station	DR Dwingeloo C Test Station	OR LOFAR2.0 [ Test Station	DR Production DR Test Station	Rollout
Location	Lab	Test field	Operational site	Operational site	
Level of verification validation		Few receiver chains and full station infrastructure	Full integrated station; Station in array	Production test; >1 stations in array	
N. active antennas	1 LBA 1 HBA Tile	9 LBAs 3 HBA Tiles	1 core station: 96 LBAs 2 x 24 HBA Tiles	2 stations	




# Dwingeloo Test Station (DTS)

- Close to the office
  - Quick debugging
- Integration of 9 receivers



## Startup sequence

- One software call to startup DTS
  - Hibernate -> On State (only)
  - Set to default configuration
- End-to-end verification thereafter
  - Readout of subband statistics
  - Full LOFAR2.0 Bandwidth
  - End-to-end: antenna control software








#### Beamforming LBA

- Beams at different elevations
- Observe sky
  - Cyg A and Cas A most prominent<sup>4</sup>
- Result:
  - Measurement matches with  $\frac{\widehat{\underline{c}}}{\underline{b}}$  8 CygA/CasA trajectories  $\underbrace{\underline{c}}_{\underline{b}}$  10 -
- Note
  - Other response is grating lobes<sup>14</sup>
  - Ionosphere blocking before T = 2 h.


DTS BST: Power (dB) in LBA Y-beam, f=50.8 MHz 0 2 -



-71.0

# Cooling challenge

- LOFAR1: shutdown of station at 28 degree
- LOFAR2.0
  - More processing  $\rightarrow$  heat production
  - Prevent shut-down at lower temperatures
- Improvements: add roof, prevent recirculation
- DTS Experiment on hot day:
  - 18 July 2022: max temp: 36.5 deg C (INT HOGEVER)
  - Perform standard observation and
  - Simulate LOFAR2.0 power dissipation
- Result: LOFAR2.0 can cope higher temperatures!
  - 50 °C  $\rightarrow$  0.05 hour downtime per year.



Not tripped!

left compartme

## Plan forward: LOFAR2.0 Test Station

- Verification of transition  $\checkmark$ 
  - Connections
    - Antennas to RCU2 inputs
    - Power
    - Network
    - Clock
  - Calibration of antennas
    - Phase and amplitude
    - Redundant baselines
  - Beamforming
    - Antenna positions
  - Rollout
    - Labels, tools, instructions

- Validation 1
  - Analog beamforming  $\checkmark$
  - End-to-end linearity
    - XST, product FM-DAB → intermodfreqs 24hour intergreren, compare with LOFAR1 → this cyclo
  - Crosstalk Low/High → this cycle
- Validation − 2 → Start next cycle
  - Crosstalk HBA sub-stations (upper lim)
  - Beamforming and Imaging
    - RECV-Low: circle for beamshape
  - Cabinet shielding
  - Antenna connection scheme



# LOFAR2.0 Test Station Analog beamformer validation

HBAT 1

HBAT 4

HBAT 0

HBAT 3

HBAT 2

HBAT 5

- Tile-beam validation with satellites scanning through the beam
- Analog beamformer test:

#### Summary

- LOFAR2.0 Upgrade
  - All antennas
  - Full bandwidth
- Verification and Validation
  - Successfull validation in Lab Test Station and Dwingeloo Test Station
  - Next step: LOFAR2.0 Test Station
- Acknowledgements
  - Wim van Cappellen, Arno Schoenmakers, Paulus Kruger, Mark Ruiter, Gijs Schoonderbeek, Jan David Mol, Marchel Gerbers, Carla Baldovin, Roel Witvers
  - And many more in the development and operations teams